

City of Haverhill MA
Emergency PS & FM Projects
W-P Project No. 22696
AACE Class 3 Estimate
 ENR Index # 14307
 Date: 8/18/2026

TOTAL PROJECT COST ESTIMATE SUMMARY

Project	PS Header ¹	FM & Site Piping ²	Total All	Comments
Construction Bid Price	\$ 2,620,000	\$ 15,200,000		
Construction Contingency ³	\$ 265,000	\$ 1,520,000		
Design Under Contract	\$ -	\$ -		\$500,000 under contract
Final Design Fee & Permitting	\$ 125,000	\$ 300,000		
Construction Engineering/Inspection	\$ 410,000	\$ 900,000		
Utility Allowance (Elec/Gas)	\$ -	\$ 500,000		
Materials Testing Allowance	\$ 20,000	\$ 150,000		
Emergency Bypass ⁴	\$ -	\$ 4,180,000		
Engineer's Estimate of Project Cost	\$ 3,440,000	\$ 22,750,000	\$ 26,190,000	

Notes:

1. Vendor costs updated, additional scope includes: 24" pipe/fittings, 36" valve on header, new wall pipe, concrete work
2. Assumes dual 36" FM & (16) 36" Gate Valves. DNI brook crossing
3. 10% of bid price assumed, note it is higher than typical construction contingency due to fast tracked project and level of unknowns
4. \$380k/mo. assumed for 11 months
5. Peabody Brook Crossing not included, placeholder \$1.2M
6. Hazardous Soil Disposal not included in cost. High range of disposal costs could be up to \$800/TN (\$8M)
7. Easements not included in cost.